

Crane Safety Committee and Lift plan procedure





Objectives

- Organize and formalize the crane safety committee
- Ensures project team performs due diligence project safety planning before crane lifts
- Create a lift plan data bank
- Establish the company lift plan procedure
- Identifies the competent person(s) on site who will be accountable for planning and ensuring proper equipment use and lift safety is maintained

Crane Committee members

- Crane committee members will be described as a company "Competent Persons".

Competent person' is defined as 'one who is capable of identifying existing and predictable hazards in the surroundings or working conditions which are hazardous, or dangerous to employees, and who has company authorization to take prompt corrective measures to eliminate them"





Crane Committee members

- Project Safety Rep.
- Project Superintendent
- Project Manager





Submit Documents

- Person in charge of lift work will submit lift plan and the appropriate documents.






Required documents

Non - Critical Lift

- Activity Hazard Analysis
- Lift Plan Form
- Crane Spec Sheet
- Crane certification of inspection
- Operator certification
- Riggers information
- Summary of the lift including description of the load



Required documents



Repetitive Non-Critical Lifts (General Hoisting)

- Standard general daily crane work for hoisting formwork, cmu, rebar, general material handling, etc.
- A specific plan would not be submitted for each pick, but rather a general lift plan based on radius, weight, standard rigging configurations, etc.
- Weights and radius to be checked and confirmed with each lift as standard practice.
- Note: Only competent riggers and signalmen shall direct the operator.
- Rigging Inspected Daily

Required documents


For Critical Lift

- Activity Hazard Analysis
- Lift Plan Form
- Crane Spec Sheet
- Crane certification of inspection
- Operator Certification of Inspection
- Riggers information
- Critical Lift Form
- Pre Lift-Meeting toolbox
- Summary of the lift including description of the load
- If man basket will be used a Load Test form should be included



Critical lift

- A critical lift is one that exceeds 75% of the rated capacity of the crane or derrick, or b) requires the use of more than one crane or derrick. ... Any lift that requires more than one crane. Loads exceeding 75% of a crane's rated capacity, Lifting of personnel, lift which required the load to be lifted, swung or placed out of the operators view, lift within 20' of power lines and involve a non-routine or technically difficult rigging arrangements





When to submit documents ?

Non critical lift

in advance



Critical lift

in advance





Required documents

Activity Hazard Analysis (AHA)

Activity/Work Task: RELOCATE MONKEY POD TREES	Overall Risk Assessment Code (RAC) (Use highest code)
Project Location: INTERNATIONAL MARKET PLACE	Risk Assessment Code (RAC) Matrix
Contract Number:	
Date Prepared: 9.16.14	
Prepared by (Name/Title): Kerwin Chong / vp	
Reviewed by (Name/Title):	
Notes: (Field Notes, Review Comments, etc.)	

Step 1: Review each "Hazard" with identified safety "Controls" and determine RAC (See above)

"Probability" is the likelihood to cause an incident, near miss, or accident and identified as: Frequent, Likely, Occasional, Seldom or Unlikely.

"Severity" is the outcome/degree if an incident, near miss, or accident did occur and identified as: Catastrophic, Critical, Marginal, or Negligible.

Step 2: Identify the RAC (Probability/Severity) as E, H, M, or L for each "Hazard" on AHA. Annotate the overall highest RAC at the top of AHA.

Job Steps	Hazards	Controls	RAC				
			Frequent	Likely	Occasional	Seldom	Unlikely
1. Delivery to Site.	Vehicular & pedestrian accidents	Mobile crane driver to use defensive driving techniques, move only with proper escorts and permits.	L				
2. Crane setup & delivery	Equipment & pedestrian accidents	Safe work zones to be provided by Owner/Contractor with access to mobile crane operator and signal man. Maintain visibility when direct line of sight between mobile crane driver and operator - especially when working in tight areas or when operator has a view of driver's blind spots. Reme for forklift operation and trailer.	L				
3. Rigging installation	Injury due to sling pinching fingers or hands.	Contractor shall verify and ensuring no underground voids, pipes, boxes, etc. prior to the operation. Operator to verify with contractor prior to set up.	M				
	Injury due to sling pinching fingers or hands.	Contractor shall use proper lifting equipment and techniques as specified by crane manufacturer.	L				
		Use heavy gloves operator shall only when directed by signal man signal man have clear view of each rigger.	L				

Activity Hazard Analysis (AHA)

Activity/Work Task: RELOCATE MONKEY POD TREES	Overall Risk Assessment Code (RAC) (Use highest code)
Project Location: INTERNATIONAL MARKET PLACE	Risk Assessment Code (RAC) Matrix
Contract Number:	
Date Prepared: 9.16.14	
Prepared by (Name/Title): Kerwin Chong / vp	
Reviewed by (Name/Title):	
Notes: (Field Notes, Review Comments, etc.)	

Step 1: Review each "Hazard" with identified safety "Controls" and determine RAC (See above)

"Probability" is the likelihood to cause an incident, near miss, or accident and identified as: Frequent, Likely, Occasional, Seldom or Unlikely.

"Severity" is the outcome/degree if an incident, near miss, or accident did occur and identified as: Catastrophic, Critical, Marginal, or Negligible.

Step 2: Identify the RAC (Probability/Severity) as E, H, M, or L for each "Hazard" on AHA. Annotate the overall highest RAC at the top of AHA.

Job Steps	Hazards	Controls	RAC				
			Frequent	Likely	Occasional	Seldom	Unlikely
LIFT TREE	High Winds (in excess of 25 mph)	Operations to be aborted if winds exceed 25 mph..	M				
	Operator unable to see	Signal Man to be dispatched for operation(s).	L				
	Rigging overload due to asymmetric rigging on branches	Use of standard crane hand signals by signal man and/or walkie-talkies equipped with unique channel for Hawaiian Crane & Rigging Ltd. only.	L				
	Tree fall over during the temporary "put down"	Use rolling blocks to equalize load and ensure equal distribution of load to rigging.	H				
		Make sure guy wires are fully engaged before releasing load off of main line of crane.	H				

Equipment to be Used	Training Requirements/Competent or Qualified Personnel name(s)	Inspection Requirements
300T DEMAG AC 250 HYDRAULIC CRANE	ANNUAL CRANE CERTIFICATE, PARKER MCKEAGUE: SOH HOIST CARD, NOGO-CERT TODD MOORE: RIGGERS CERTIFICATION	CRANE ANNUAL INSPECTION AND LOAD TEST
NEED CERTS.		
Prepared by (Print Name, Sign and Date): _____		
Crew Supervisor Review (Print Name, Sign and Date): _____		
AHA Discussed with Crew at Preparatory Meeting Held On: _____		
Sign: _____	Sign: _____	Sign: _____
Print: _____	Print: _____	Print: _____
Sign: _____	Sign: _____	Sign: _____
Print: _____	Print: _____	Print: _____
Sign: _____	Sign: _____	Sign: _____
Print: _____	Print: _____	Print: _____

AHA
(Activity Hazard Analysis)

Required documents



LIFTING PLAN

NOTE: A LIFT PLAN SHOULD BE COMPLETED PRIOR TO MOBILIZATION OF EQUIPMENT AND RIGGING

Location:	Angeles Pkwy		
Load Description:	Electrical Man Hole Cover Installation		
Lift Description:	Lift Electrical Man Hole concrete cover from Ground and set in top of the man hole		
Date of Lift:			
A. WEIGHT			
1. Equipment Conditions:	New <input type="checkbox"/> Used <input checked="" type="checkbox"/>	LBS:	
2. Weight Empty:	0 LBS		
3. Weight of Headache Ball:	600 LBS.		
4. Weight of Block:	0 LBS.		
5. Weight of Lifting Bar:	0 LBS.		
6. Weight of Slings and Shackles:	36 LBS.		
7. Weight of Load:	0 LBS.		
1.1 Total Weight of Load:	600 LBS.		
8. Weight of Headache Ball on Jib:	0 LBS.		
9. Load of Counter:	144 LBS.		
10. Allowance for Unaccounted Material or Equipment	0 LBS.		
Concrete cover	10000 LBS.		
Total Weight:	10760 LBS.		
B. JIB			
Encoder <input type="checkbox"/> Stored <input checked="" type="checkbox"/>			
1. Is Jib to be used:	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		
2. Length of Jib:	0 FT.		
3. Angle of Jib:	0 DEG.		
4. Rated Capacity of Jib: (From Chart)	0 LBS.		
C. Crane Placement			
1. Any Deviations From Smooth Solid Foundation in the Area? No			
2. Electrical Hazards in the Area? N/A			
3. Obstacles or Obstructions to Lift and Swing? N/A			
4. Swing Direction and Degree (Boom Swing) south west to south east			
D. CABLE			
1. Number of Parts Cable:	4		
2. Size of Cable:	5/8"		
E. Sizing of Slings			
1. Sling Selection	wire rope 1/2"		
a. Type of Arrangement	4 x 5 # each		
b. Number of Slings and Weight	4 x 5 # each		
c. Sling Size	V2"		
d. Sling Length	10'		
e. Rated Capacity of Sling	62000 each		
Shackles Attached to Sling			
a. Pin Diameter (inches)	.5 - 1" each		
b. Capacity (tons)	1 ton each		
c. Weight of the rigging	7000		
F. CRANE			
1. Type of Crane	Terex RT 160		
2. Crane Capacity	60 ton		
3. Lifting Arrangement			
a. Max Distance, Center of Load to Center Pin of Crane	30'		
b. Length of Boom	75'		
c. Angle of Boom at Pick-up	62°		
d. Angle of Boom at Set	62°		
e. Rated Capacity of Crane Under Severe Lifting Conditions (From Chart)			
1. Over Rear	35.3		
2. Over Front	35.3		
3. Over Side	35.3		
4. From Chart - Rated Capacity of Crane For This Lift	35,300		
5. Max. Load On Crane	10760		
6. Lifts:	0		
7. max lift weight for 75% of Crane Capacity	0.31		
8. Crane Capacity	26475		
G. PRE-LIFT CHECK LIST			
1. Lifting Acceptable? N/A	YES / NO		
2. Outriggers Fully Extended? YES			
3. Crane in Good Condition? yes			
4. Swing Room? Y			
5. Head Room Checked? Y			
6. Max Counterweights Used? Y			
7. Tag Line Used? Y			
8. Experienced Operator? Y			
9. Duties and Responsibilities Assigned? Y			
10. Experienced Rigger? Y			
11. Load Chain in Case? Y			
12. Wind Condition - SM MPH			
13. Tele Handler Inspected By			
14. Functional Test of Crane By:			

Special Instructions or Restrictions for Crane, Rigging, Lift, Etc...

Tag Lines and Rigger, Gusting winds up to 20 mph - use anemometer and stand-down if winds > 25 mph

Diagram Crane and Load Placement	Diagram Rigging Configuration
----------------------------------	-------------------------------

* Multiple Crane Lifts Require a Separate Lift Plan for Each Crane.

* Any Changes In The Configuration Of The Crane, Placement, Rigging, Lifting Scheme, Etc., Or Changes In Any Calculations Requires That A New Lift Plan Be Developed.

x Date: _____ Date: _____

Signature of Job Supervisor

Signature - Plan Checked By

Operator certification and Lift plan form



Required documents

Lift Plan Summary

Cap Juluca

Concrete Piles

Lift Plan

Transformer Lift Plan Summary

Work to be done

Lift Concrete piles and set it on a flat bed .

Crane Model and Capacity

Terex RT 160 -60 Ton Capacity

Load Description

Pre-cast concrete piles 5,000 #

Work Radius

75'

Boom Length and angle

115' - (46°)

Total Weight calculation	Transformer unit	5000 #
	Crane cable	60 #
	Wire Rope Slings	6#
	Ball	476#
	Shackles	4#
Total		
		5546 # /

Crane Cap by Chart 8200# = **0.67%** crane cap.

Based on crane calculations, additional 604# can be add to the load to reach the 75% if necessary.

Tag line will be necessary to control the load. Lift plan to be cancelled if wind speed is 25 MPH or more sustain.

9/16/ Wire rope Sling to be connected on vertical one leg via 5/8 shackle .

Calculation of the slings.


Sling to be used vertical . Load = 5000 . 9/16 wire rope sling =6400 #cap or Synthetic Web sling 6" =6000 # cap.

Concrete pile will be lifted from the form and set in a flat bed to be transported to the installation area at the beach . Once the truck arrived to the beach , piles will be lifted with an excavator and set it in the correct place.





Required documents

Lift Plan Sketch




Approval process

- Once documents are submitted, the committee will reply to approved or request more information if necessary. Once the reviewers have the proper documentation then an approval will be given to go or no go.






Approval





Approved lift plan and data bank

COMPANY	: PT. SILO		
PROJECT	: SEBUKU SINTERING PROJECT		
MAT'L NAME	: COAL BIN TANK		
LOCATION	: WEST OF RAW COAL		
DATE OF ERECTION	:		
LIFTING DATA			
NO.	DESCRIPTION	CRANE	
I.	CRANE TYPE AND MODEL	TADANO TR-350M 35 TON	
II.	ERCTION LOAD	1. Erection Weight 2. Weight of Shackle / Sling 3. Weight of Hook Block 4. Weight of Spreader Beam / Chain Block	
	TOTAL LOAD	6.2 Ton	
III.	CRANE DATAS	1. Crane Capacity 2. Crane Condition 3. Main Boom 4. Load line reeving 5. Working Radius 6. Lifting Capacity	
IV.	SAFETY FACTOR (Lift. Cap X Crane Condition)	1.2 Total Load	
V.	LIFTING DEVICE	1. Sling Wire Size (dia x length) 2. Sling Quantity to be use 3. Sling Wire (Safe Working Load) 4. Shackle (Safe Working Load) 5. Spreader / Lifting Beam (SWL)	
VI.	METHODE OF COMMUNICATION TO BE USED	Radio	
VII.	GROUND CONDITON	Level	
PREPARED BY;		CHECKED BY;	APPROVED BY;
(M. SYAIFUR ROKHIM)		(_____)	(_____)



Summary


Plan with your local team.



Determine if is a non-critical or critical lift.




Submit the appropriate documentation to the crane committee on a timely manner 48 hrs. for NCL 72 for CL






Summary


Crane Committee will approve or request more documentation .




Discuss with the crane committee the requirements.



Once approved , proceed to do the work following all the requirements as established in the lift plan.



Crane Committee will upload the documents to the lift plans link for future reference .





Questions

